

CONSULTANTS & CONTRACTORS



## **Tree Survey**

### At

## The Custom House Penarth

THE VALE OF GLAMORGAN COUNCIL (PLANNING DIVISION)

RE-REGISTERED

HEAD OF PLANNING AND TRANSPORTATION

MICEIVED

2 0 DEC 2011

ENCTRONMENTAL AND ECONOMIC RECEPTORALIZATION

Inspected by:Julian Wilkes BSc. For, MSc. Land Man, MIC. For, MArborA
Treescene Ltd
The Walled Garden
Old Coedarhydyglyn
St Nicholas
Cardiff
CF5 6SG
Tel No. 029 20599300

27 October 2011

Registered Office: Treescene Limited

The Walled Garden, Old Coedarhydyglyn, St Nicholas, Cardiff CF5 6SG
Tel. 029 205 99300 Fax. 029 205 92929 Email. trees@treescene.co.uk

I have been instructed by Mr Nigel Arnold of Nigel Arnold Architects to carry out a survey on trees at The Custom House, Penarth

#### Scope of Report

This Tree Survey has been undertaken within the recommendations of British Standards 5837:2005 and current good arboricultural practice.

The survey entailed a visual inspection from ground level of all trees.

Each tree has been numbered and, where instructed, for future identification on site, have been tagged using small durable metal or plastic tags.

Due to variations of existing ground levels through the site, height dimensions are estimated and are given in metres. Accurate heights, measured with the aid of optical instruments can be provided where instructed.

Trunk/stem diameters are measured at 1.5 metres above ground level, or immediately above the root flare for multi-stemmed trees.

Estimate branch spread is taken in metres from the centre of the trunk, at the four cardinal points of a compass, to achieve an accurate representation of crown shape.

An assessment of a tree's age classification is made in terms of it maturity within the site's landscape.

An assessment of a tree's physiological condition is to be made as good, fair, poor, dead.

Data on the structural condition of the tree should be entered, e.g., collapsing, leaning and the presence of any decay or physical defect should be noted.

Preliminary management recommendations include further investigation of suspected defects that require more detailed assessment and potential for wildlife habitat.

An assessment of a tree's future life expectancy is made as <10, 10-20, 20-40 or >40 etc.

The category for each tree is assessed using the recommendations of BS5837:2005.

assassmont	
e quality	
tree	
art for	
le ch	
Cascad	
ble 1	
Taj	

	TREES FOR REMOVAL				
	Category and definition.		Criteria		Mantification
	Category R	* Trees that have a serious, irrem	ve a serious, igremediable, structural defect such that their		plan
8	any existing value would be lost within 10 years and which.	including those that will become unviable after removal of loss of companion shelter cannot be mitigated by pruning)	that will become unviable after removal of other R category trees (i.e. where, for whatever reason, the on shelter cannot be mitigated by pruning)	is expected due to collapse, where, for whatever reason, the	DARKRED
128	eshould, in the current context, he removed for reasons of sound arboricultural management	<ul> <li>Trees that are dead or are showing signs of significant, immediate,</li> <li>Trees infected with pathogens of significance to the health and/or sor very low quality trees suppressing adjacent trees of better multip.</li> </ul>	<ul> <li>Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline</li> <li>Trees infected with pathogens of significance to the health and/or safety of other trees nearby (e.g. Dutch elm disease), or very low quality trees suppressing adjacent trees of better musity.</li> </ul>	overall decline s nearby (e.g. Dutch elm disease),	2 2 2
		NOTE Habitat reinstatement may be tree;	NOTE Habitat reinstatement may be appropriate (e.g. R category tree used as a bat roost: installation of bat box in nearby tree).	t: installation of bat box in nearby	
	TREES TO BE CONSIDERED FOR RETENTION	FOR RETENTION			
	Category and definition .				
		Water bearing and a second	Criteria — Subcategories		Identification on
1	A succession A	a manny arboricultural values	2 Mainly landscape values	3 Mainly cultural values, including conservation	. plan
	Those of high quality and	Trees that are particularly good	Trees, groups or woodlands which provide a	Trees, groups or woodlands of	
	value: in such a condition as to	if rare or unusual, or essential	demnite acreening or softening effect to the locality in relation to views into or out of the site or those	significant conservation;	
	contribution (a minimum of 40	components of groups, or of formal or semi-formal arboricultural	of particular visual importance (e.g. avenues or	other value (e.g. veteran trees or	LIGHT GREEN
	years is suggested)	features (e.g. the dominant and/or principal trees within an avenue)	come and included as groups)	Wood-pasture)	Secret on
	Category B	Trees that might be included in the			
	Those of moderate quality	high category, but are downgraded	Woodlands, such that they form diefficel and	Trees with clearly identifiable	
	condition as to make a significant	because of impaired condition (e.g.	features, thereby attracting a higher collective	conservation or other cultural	MID BLUE
	contribution (a minimum of 20	including unsympathetic past	rating than they might as individuals but which		
	years is suggested)	management and minor storm	formal or semi-formal arboricultural features of	4	
		damage)	trees of moderate quality within an avenue that		
			situated mainly informally to the city, the city		
7.56			individually having little visual impact on the		
*	Category C	Trees not qualifying in higher	Transmitter		
	value; currently in adamate	categories	this conferring on them significantly greater	Trees with very limited.	
	condition to remain until new		landscape value, and/or trees offering low or only	benefits	GREY
1	planting could be established (a	NOMB true	remporary screening benefit		
5	minimum of 10 years is	development, young trees with a ster	development, young trees with a stem diameter of the where they would impose a significant constraint on	ignificant constraint on	
	stem diameter below 150 mm		and the state of the second of	d for relocation.	

T1 Height	Sycamore (Acer pseudoplatanus) 17m
Single/Multi stemmed	Single stem
Stem Diameter	0.44m
Branch Spread	N-4m
	E-3m
	S-2m
	W-4m
Height of Crown	3m
Age	Middle aged
Physiological Condition	Fair to poor
Structural Condition	Tree of variable form. Main stem divides at 3m leading to twin stem mid crown. Evidence of minor squirrel damage and associated deadwood throughout crown.
Prel. Man. Recommendations	Prune to remove major deadwood and damaged branches.
	Monitor for health
Est. Remaining Contribution	20-40
Category	C2

T2	Sycamore (Acer pseudoplatanus)
Height	18m
Single/Multi stemmed	Multi stemmed
Stem Diameter	0.6m
Branch Spread	N-4m
	E-6m
	S-7m
	W-6m
Height of Crown	1m
Age	Middle aged
Physiological Condition	Fair to poor
<b>Structural Condition</b>	Multi stemmed specimen of variable form with evidence of
	tight forks and inclusions at base. Extensive ivy growth
	on main stems prevents full inspection.
Prel. Man. Recommendations	No action required at this time. Monitor basal forks for
	safety.
Est. Remaining Contribution	20-40
Category	C2

T3 Height Single/Multi stemmed Stem Diameter Branch Spread	Sycamore (Acer pseudoplatanus) 16m Single stem 0.41m N - 4m E - 4m S - 5m W - 3m
Height of Crown Age Physiological Condition Structural Condition  Prel. Man. Recommendations Est. Remaining Contribution Category	8m Middle aged Fair to poor Tree of reasonable form with extensive epicormic shoots at base that prevent full inspection. This specimen has grown into adjacent iron railing fence which may have led to structural deformities within main stem.  Monitor for health 10-20 C2
G4 Height Single/Multi stemmed Stem Diameter Branch Spread  Height of Crown Age Physiological Condition Structural Condition	Group of Sycamore (Acer pseudoplatanus)  11m  Single and multi stemmed  Up to 0.3m  N - 2m  E - 2m  S - 0m  W - 1m  1m  Young  Poor  Trees of poor form sited on steep slope. These specimens

may become unstable at a later date.

Remove

<10 R

Prel. Man. Recommendations

Est. Remaining Contribution Category

T5	Sycamore (Acer pseudoplatanus)
Height	17m
Single/Multi stemmed	Multi stemmed
Stem Diameter	0.45m
Branch Spread	N-4m
	E-5m
	S-2m
	W-1m
Height of Crown	0m
Age	Middle aged
Physiological Condition	Fair to poor
Structural Condition	Tree of poor form with minor stem extending from base on
	the western side. Secondary branch extends on the eastern
	side at approximately 3m which also exhibits signs of decay at
	approximately 9m
Prel. Man. Recommendations	Remove damaged branch on eastern side. Monitor for health
Est. Remaining Contribution	10-20
Category	C

T6	Ash (Fraxinus excelsior)
Height	13m
Single/Multi stemmed	Single stem
Stem Diameter	0.21m
Branch Spread	N-0m
System Budderspare as electrical action extension and	E-8m
	S-0m
	W - 0m
Height of Crown	10m
Age	Middle aged
Physiological Condition	Poor
Structural Condition	Tree of poor form with notable twists within main stem.
	This specimen may become unstable
Prel. Man. Recommendations	Remove
Est. Remaining Contribution	<10
Category	R

<b>T7</b>	Sycamore (Acer pseudoplatanus)
Height	17m
Single/Multi stemmed	Single stem
Stem Diameter	0.47m
Branch Spread	N-5m
•	E-7m
	S-3m
	W-1m
Height of Crown	4m
Age	Middle aged
Physiological Condition	Fair
Structural Condition	Tree of reasonable form with crown more heavily developed
	on eastern side. Main stem heavily colonised by ivy thus
	preventing full inspection
Prel. Man. Recommendations	Sever ivy at base. Monitor for stability
Est. Remaining Contribution	>40
Category	B2
- V	
Т8	Sycamore (Acer pseudoplatanus)
Height	16m
Single/Multi stemmed	Single stem
Stem Diameter	0.35m
Branch Spread	N-3m
	E-4m
	S-4m
	W-3m
Height of Crown	8m
Age	Middle aged
	<u> </u>

Remove

<10

R

Tree of reasonable form with extensive decay within main stem

at approximately 1m. This specimen it at risk of failure

Physiological Condition Structural Condition

Category

Prel. Man. Recommendations

Est. Remaining Contribution

Т9	Ash (Fraxinus excelsior)
Height	18m
Single/Multi stemmed	Single stem
Stem Diameter	0.44m
Branch Spread	N-8m
-	E-8m
	S-3m
	W-2m
Height of Crown	10m
Age	Middle aged
Physiological Condition	Fair to poor
Structural Condition	Tree of poor form with crown heavily developed on northern
	side. This specimen leans extensively to the north. Main
	stem heavily colonised by ivy thus preventing full inspection.
Prel. Man. Recommendations	Undertake 7m crown reduction to reduce risk of failure.
	Monitor for health.
<b>Est. Remaining Contribution</b>	20-40
Category	C
00 00 00 00 00 00 00 00 00 00 00 00 00	

T10	Sycamore (Acer pseudoplatanus)
Height	18m
Single/Multi stemmed	Single stem
Stem Diameter	0.51m
Branch Spread	N-6m
	E-6m
	S-4m
	W-5m
Height of Crown	6m
Age	Middle aged
Physiological Condition	Fair
Structural Condition	Tree of reasonable form with well balanced crown. Main stem heavily colonised by ivy thus preventing full inspection.
	Evidence of minor deadwood within crown.
Prel. Man. Recommendations	Sever ivy at base. Prune to remove deadwood. Monitor
A POR IVEGER PROCESSION	for health.
Est. Remaining Contribution	>40
Category	B2

Sycamore (Acer pseudoplatanus) T11 Height Multi stemmed Single/Multi stemmed 0.5m**Stem Diameter Branch Spread** N-3mE-4mS-3mW - 3mHeight of Crown 0mMiddle aged Age Poor **Physiological Condition** Multi stemmed specimen of poor form with extensive squirrel **Structural Condition** damage throughout crown. This specimen is unsuitable for retention Prel. Man. Recommendations Remove **Est. Remaining Contribution** < 10 R Category

Ash (Fraxinus excelsior) T12 19m Height Single stem Single/Multi stemmed 0.47m Stem Diameter N-5m**Branch Spread** E-5mS-8mW - 3mHeight of Crown 6m Middle aged Age **Physiological Condition** Tree of reasonable form sited at top of steep bank **Structural Condition** No action required at this time Prel. Man. Recommendations Est. Remaining Contribution >40 B2 Category

T13 Height	Sycamore (Acer pseudoplatanus) 18m
Single/Multi stemmed	Single stem
Stem Diameter	0.44m
Branch Spread	N-5m
Dianen Spicau	E-4m
	S – 5m
	W-4m
Height of Crown	2m
Age	Middle aged
Physiological Condition	Fair to poor
Structural Condition	Tree of variable form with some minor squirrel damage
Structural Condition	within crown. Ivy colonisation of base and main stem
	prevents full inspection
Prel. Man. Recommendations	No action required at this time. Monitor for health
Est. Remaining Contribution	20-40
Category	C2
Category	C2
T14	Sycamore (Acer pseudoplatanus)
Height	15m
Single/Multi stemmed	Multi stemmed
Stem Diameter	0.5m
Branch Spread	N-3m
	E-2m
	S-4m
	W-5m
Height of Crown	3m
Age	Middle aged
Physiological Condition	Fair to poor
Structural Condition	Tree of variable form. Main stem divides at 0.5m leading to
	multi stemmed mid crown. Evidence of severe inclusions
	within these basal forks. Extensive ivy colonisation
	prevents inspection on base at main stem. Evidence of
0	severe squirrel damage throughout crown.
Prel. Man. Recommendations	Undertake 5m crown reduction. Sever ivy at base. Monitor
	for health
Est. Remaining Contribution	10-20
Category	C


T15 Sycamore (Acer pseudoplatanus) Height 16m Single/Multi stemmed Multi stemmed Stem Diameter 0.55m **Branch Spread** N-5mE-4mS-5mW - 5mHeight of Crown 3m Middle aged **Physiological Condition** Fair to poor Structural Condition Multi stemmed specimen of poor form with evidence of squirrel damage throughout mid crown Prel. Man. Recommendations Prune to remove damaged and hung up branches. Prune to remove major deadwood. Sever ivy at base. Monitor for health **Est. Remaining Contribution** 10-20 Category C

#### Recommendations for Tree Protection during Development

Due to the high risk to established trees we would recommend the installation of protective fencing prior to commencement of <u>any</u> works on site in accordance with BS 5837:2005 "Trees in relation to Construction". Trees should be protected using scaffold frame supporting weld mesh panel fencing sited on the edge of the Root Protection Area as defined in BS5837:2005. These fenced areas should not be used for the storage of any plant machinery or materials and personnel should be excluded at all times; these fences should remain in situ until after final landscaping has been carried out, removed by hand with great care to prevent compaction or root damage to established trees. The services of a suitably qualified arborist should be sought <u>prior</u> to the commencement of each stage.

### BS5837:2005 - 'TREES IN RELATION TO CONSTRUCTION -RECOMMENDATIONS'

# PROTECTIVE BARRIER - DETAIL



- 2 Uprights to be driven into the ground
- 3 Panels secured to uprights with wire ties and where necessary easy dismantling standard scaffold clamps 7 Ground level
- 4 Weldmesh wired to the uprights and horizontals
- 5 Standard clamps
- 6 Wire twisted and secured on inside face of fencing to avoid
- 7 Ground level
- 8 Approx. 0.6 m driven into the ground

Figure 2 — Protective barrier