

**THIS WORKING DRAWING IS TO BE READ IN CONJUNCTION WITH THE CREST STANDARD
CONSTRUCTION NOTES AND THE STANDARD WORKMANSHIP AND MATERIALS SPECIFICATION**

NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL
RELEVANT ARCHITECTS' ENGINEERS' SERVICES AND
SPECIALIST DRAWINGS AND SPECIFICATION.
2. ANY DISCREPANCIES IN DIMENSIONS OR DETAILS ON OR
BETWEEN THESE DRAWINGS SHOULD BE DRAWN TO THE
ATTENTION OF THE ARCHITECT AND / OR THE ENGINEER
FOR CLARIFICATION.
3. ALL DIMENSIONS ARE IN METRES UNLESS NOTED
OTHERWISE.
4. DO NOT SCALE THIS DRAWING.

KEY

— PHASE 3 RED LINE BOUNDARY

BOUNDARY TYPES

- - - 1.8m HIGH CLOSE BOARDED FENCE (REFER
TO STANDARD DETAIL DRAWING CUSD/15)
- - - INDEPENDENTLY FIRED GATE (0.8m WIDE
GATES TO INDIVIDUAL DWELLINGS, 1.8m
WIDE GATE TO FOOTWAYS)

- - - 1.8m HIGH BRICK WALL (REFER TO
STANDARD DETAIL DRAWING CUSD/130)

- - - 0.6m HIGH BRICK WALL (REFER TO
STANDARD DETAIL DRAWING CUSD/130)

- - - 900mm HIGH POST AND WIRE FENCE
WITHIN HEDGEROW

- - - 6m WIDE AUTOMATED STEEL SWING GATE
WITH REMOTE CONTROL ACCESS POINT
W2 GATE BY PORT COLUMNS WITH
CROSS BRASS STEEL FINISH OR EQUIVALENT
APPROVED

T4	BOUNDARIES ADJUSTED TO ALLOW FOR REMOVED GARAGE CREDENTIA	24.07.14	LA
T3	GATES ADDED BETWEEN PLOTS 38 & 39 AND BETWEEN PLOT 39 AND BLOCK D TO STANDARD DETAIL DRAWING CUSD/15 HANDRAILS ADDED TO STEPS	27.05.14	LA
T2	PAVING WALLS NEAR HEDGEROWS REDUCED IN HEIGHT TO ADDRESS A519 COMMENT	21.10.13	LA
T1	REVISED TO A519 CO-ORDINATION	11.10.13	LA
Rev.	Description	Date	Initial
	Crest Nicholson Ltd Crest House Lime Kiln Chase Stoke Gifford Bristol BS34 5ST Internet: www.crestnicholson.com Tel: 01179 238600 Fax: 01179 657592		
Site/Issue type: PERMARTH/ PHASE 3			
Proj title: PHASE 3 - BOUNDARY SCHEDULE			
Unit type:	Unit size:	sqm	sqft
Scale: 1:250	Date: JULY 13	Drawn: JC	Checked: JR
CAD Ref: 11845PA-PH3-3000-00	NBEC Approval Ref:		
Drawing No: 11845PA-PH3-3000-00	Revision: T4		

