## **OUTLINE PLANTING SPECIFICATION**

To be read in conjunction with: LANDSCAPE AND VISUAL IMPACT ASSESSMENT AND LANDSCAPE MANAGEMENT PLAN.

TIMING: All planting is to be carried out during November-March, inclusive

VEGETATION CLEARANCE: In areas to be planted, all grass and other herbaceous vegetation shall be cut to a height of between 50 mm and 75 mm and the arising's removed. Prior to applying herbicide the contractor shall await active vegetative re-growth sufficient for the herbicide to be at its

WEED CONTROL: The Contractor shall apply a non-residual translocated herbicide to all areas to be planted and seeded between 21 and 25 days prior to planting. The treatment for total herbicide control shall kill all treated growth including their root systems. The Contractor shall not commence any excavation or cultivation of the areas where herbicide has been applied until the vegetation has been effectively controlled.

TOPSOIL AND CULTIVATION: Existing soil to be used, imported topsoil not required. Cultivate the soil of all areas prior to seeding. This should include loosening, aerating and breaking up soil into particles 2-8mm to depths of 150mm. Remove any undesirable material brought to surface to a depth of 100mm including visible weeds, roots and large stones or clay balls with any dimension exceeding 30mm. Final cultivation prior to seeding topsoil shall be brought to a fine tilth by approved mechanical means or by hand raking, and if necessary re-grading of the surface will be carried out to conform to the prescribed finished levels.

PLANT PROTECTION: Where new planting is taking place in the vicinity of grazing stock all new planting needs to be protected by a temporary post and wire fence during its establishment. All trees and shrubs to be protected against rabbit grazing by using Tubex shelters. For suggested sizes refer to

## TREE PLANTING:

- All trees to consist of heavy standard trees planted in pits at the base of hedgerows, with depth of 500mm and width of 600mm.
- The base of each pit to be broken up to 150mm with all topsoil thoroughly broken up from the carefully excavated material, and any soil prior to backfilling.
- Trees shall be secured in position using round timber stakes (top diameter of 50-75 mm), peeled of bark, straight in length and free of snags, pests and diseases; with adjustable 25mm tree ties, made of black PVC or reinforced rubber
- Stakes for all trees shall be firmly driven and positioned into the tree planting pit before planting to a minimum depth of 300 mm below the bottom of the pit.
- The stake shall be positioned off centre on the prevailing windward side of the tree as near to the tree as possible but shall not interfere with the free movement of the branches and shall cause no rubbing.

## WOODLAND BELT PLANTING

Woodland belt planting to consist of translocated stools/stumps from the areas of existing woodland being removed (refer to Cog Moors WwTW AAD Arboricultural Report for details of woodland being removed) and new planting material. Translocation should be undertaken as follows;

- Translocation work to be undertaken in September/October
- Trees identified as suitable for translocation to be coppiced; Stump/stools to be dug out using demountable buckets and placed
- Stumps/stools will be place within excavated pits appropriate to each ones' size. Pits to be backfilled with topsoil.
- Stumps/stools to be placed at 5m centres and arranged in a random
- Areas identified as Woodland Belt Planting that cannot be covered by translocated trees will be planted using new planting material (see
- TREE PLANTING for details)

Root | Height | Brks | Age | Girth

## PLANTING SCHEDULES Tree Planting

Quercus robur

belt planting;

⊃runu	Prunus avium		Wild Cherry	BR	175-200	5	2x	8-10cm	Standard	5	
	land Belt of woodla	•	under planted -	-1210	2m²						
%	Name		Common Na	me	Size			Height (cn	ight (cm) Spacing (		
24	Corylus avellana		Hazel		1+1 Forestry transplant; Bare root; .			40-60	1.5	1.5	
24	Quercus robur		Pedunculate	Pedunculate Oak		1+1 Forestry transplant; Bare root; .			1.5	1.5	
6	Carpinus betulus		Hornbeam	Hornbeam		2L Pot; 1.5m spacing.			1.5	1.5	
6	Crataegus monogyna		Hawthorn	Hawthorn		1+1 Forestry transplant; Bare root; 1.5m spacing.			1.5	1.5	
5	Prunus	avium	Wild Cherry	Wild Cherry		1+1 Forestry transplant; Bare root; .			1.5	1.5	
4	Ligustru	ım vulgare	e Wild Privet	Wild Privet		1+1 Forestry transplant; Bare root; .			1.5	1.5	
4	Malus s	ylvestris	Crab Apple	Crab Apple		1+1 Forestry transplant; Bare root; .			1.5	1.5	
4	Viburnu	m lantana	a Wayfaring-T	Wayfaring-Tree		1+1 Forestry transplant; Bare root; .			1.5	1.5	
4	Acer campestre		Field Maple	Field Maple		1+1 Forestry transplant; Bare root; .			1.5	1.5	
3	Sorbus aucuparia		a Rowan	Rowan		1+1 Forestry transplant; Bare root; .			1.5	1.5	
3	Comus sanguinea		ea Dogwood	Dogwood		1+1 Forestry transplant; Bare root; .			1.5	1.5	
2	Lonicera periclymenum		Honeysuckl	Honeysuckle		2L pot; planted close enough to another tree, shrub or fence to allow use for support.			1.5	1.5	
2	Frangula alnus		Alder Buckt	Alder Buckthorn		1+1 Forestry transplant; Bare root; .			1.5	1.5	
2	Rhamnus cathartica		Buckthorn	Buckthorn		1+1 Forestry transplant; Bare root; .			1.5	1.5	
2	Euonymus europaea		Spindle	Spindle		1+1 Forestry transplant; Bare root; .			1.5	1.5	
2	Prunus padus		Bird Cherry	Bird Cherry		1+1 Forestry transplant; Bare root; .			1.5	1.5	
2	Sambuo	cus nigra	Elder		1+1 Forestr Bare root; .	ytransp	olant;	40-60	1.5	,	
1	llex aquifolium		Holly	Holly		2L Pot; 1.5m spacing.			1.5	1.5	
1	Hedera :	helix	lvy		2L pot; pla enough to tree, shrub	another	r	40-60	1.5	<u> </u>	

allow use for support.

